




FINAL ELECTRICAL CAPACITY = **48 KVA** → **E**  
 APEX PROPERTY RECOMMENDS HEATING BY KEROSENE OR GAS SO AS NOT TO EXCEED AVAILABLE ELECTRICAL CAPACITY  
 MAX. PERMITTED NO. OF ONSEN BATHS = **2 BATH** → **ON**  
 (1 BATH = 1.8 m<sup>3</sup>)

**UTILITIES LEGEND**  
**E** ELECTRICITY  
**I+T** INTERNET + TELEPHONE  
**W+D** WATER + DRAINAGE  
**ON** ONSEN



NOTE: ALL HEIGHT LIMITS TO BE MEASURED FROM LOWEST POINT AT WHICH THE BUILDING TOUCHES THE GROUND TO THE HIGHEST POINT OF THE ROOF, PER KUTCHAN TOWN DEVELOPMENT REGULATIONS.

**KUTCHAN TOWN PLANNING REGULATIONS**

**DEVELOPMENT ZONE :** WEST IWAOBETSU, ASAHI, HANAZONO AREA  
**MAX. COVERAGE RATIO :** (TOWN COVERAGE RATIO IS SUPERCEDED BY FOREST LAW; REFER MAX. BUILDING FOOTPRINT)  
**MAX. FLOOR AREA RATIO :** 200% (50% FOR "HOTEL" BUILDING PERMIT)\*  
**MAX. HEIGHT :** 13 m  
**MIN. ROAD SETBACK :** 2 m (COVERAGE < 200 m<sup>2</sup>)  
 4 m (200 m<sup>2</sup> < COVERAGE < 700 m<sup>2</sup>)  
**MIN. SIDE SETBACK :** 1.5 m (HEIGHT < 7m); 2.0 m (HEIGHT >= 7m)  
 5.0 m ("HOTEL" BUILDING PERMIT)\*  
**ROAD SHASEN LINE RATIO:** 1.25:1\*  
**SIDE SHASEN LINE RATIO:** 1.25:1 @ 20m HEIGHT ABOVE BOUNDARY

**FOREST DEVELOPMENT LAWS**

**MAXIMUM DEVELOPMENT FOOTPRINT (30% DEV. AREA) = 361.39 m<sup>2</sup>**  
**MAXIMUM FOREST CLEARANCE (INCL ROAD CUT/FILL) = 502.37 m<sup>2</sup>**  
**ALL REMAINING FOREST IS TO BE PRESERVED.**  
**FOREST WHICH IS CLEARED FOR CONSTRUCTION PURPOSES TO BE REPLANTED.**

**ADDITIONAL HANACREEK PLANNING CONTROLS**



**BUILDING TYPE:** RESIDENCE (2-KEY OPTION PERMITTED)  
**LAND & ROOF DRAINAGE :** DRAINAGE SHALL NOT FALL TOWARDS ROAD

**NOTES:** ALL AREAS AND DIMENSIONS & CAPACITIES ARE SUBJECT TO CHANGE DEPENDING ON FINAL AUTHORITY & ENGINEERING REQUIREMENTS.  
 \* NEW REGULATIONS EXPECTED TO BE ENACTED BY KUTCHAN TOWN IN 2023





**Hanacreek LOT 7**  
**1,969.90 m<sup>2</sup>**  
**(1,204.62 m<sup>2</sup> DEVELOPABLE AREA)**






**SECTION A - VIEW TO MT.YOTEI**




**SECTION B - VIEW TO MT. NISEKO-ANNUPURI**



**KUTCHAN TOWN PLANNING REGULATIONS (HEIGHT & SHASEN SLOPE LINES)**  
**DEVELOPMENT ZONE :** WEST IWAOBETSU, ASAHI, HANAZONO AREA  
**MAX. HEIGHT :** 13 m  
**ROAD SHASEN LINE RATIO:** 1.25:1\*  
**SIDE SHASEN LINE RATIO:** 1.25:1 @ 20m HEIGHT ABOVE BOUNDARY

**NOTES REGARDING VIEW LINES TO MOUNTAINS:**  
 1. BUILDING FORMS ARE INDICATIVE MAXIMUM HEIGHT VOLUMES ONLY, AND ARE SET OUT FROM THE LOWEST POINTS OF EXPECTED BUILDING FOOTPRINTS.  
 2. VIEW LINES ARE APPROXIMATE ONLY AND DO NOT TAKE INTO ACCOUNT OBSTRUCTION BY TREES. VIEWS TO MOUNTAINS CANNOT BE GUARANTEED.  
 3. ACTUAL BUILDING VOLUMES ON OTHER LOTS MAY PARTIALLY INTRUDE INTO VIEW LINES IF CONSTRUCTED OUTSIDE ASSUMED BUILDING FOOTPRINTS.


**NOTES REGARDING LOT INFORMATION AND AUTHORITY REGULATIONS:**  
 1. ALL AREAS, DIMENSIONS & CAPACITIES ARE SUBJECT TO CHANGE DEPENDING ON FINAL AUTHORITY & ENGINEERING REQUIREMENTS.  
 2. ALL APPLICABLE REGULATIONS TO BE CONFIRMED BY THE BUYER.  
 3. \* NEW REGULATIONS EXPECTED TO BE ENACTED BY KUTCHAN TOWN IN 2023



**HANACREEK**  
NISEKO

# Hanacreek LOT 7

**1,969.90 m<sup>2</sup>**  
(1,204.62 m<sup>2</sup> DEVELOPABLE AREA)



**APEX**  
PROPERTY